

The Compact Accelerator based Neutron Source (CANS) project “LvB” at Martonvásár, Hungary

Zs. Ludányi¹, G. Anda², E. Dian¹, Á. Horváth², R. Mezei¹, L. Rosta², H. Shuai¹, P. Sipos¹, G. Szász¹ and F. Mezei¹

¹Mirrotron Ltd., Hungary

²Centre for Energy Research, Hungary

**Neutron Delivery Systems NDS 2023 @ ILL
10-12 July 2023**

The Compact Accelerator based Neutron Source (CANS) project “LvB” at Martonvásár, Hungary

Outline: Introduction

Motivation

Design

Construction status

Further plans

**Neutron Delivery Systems NDS 2023 @ ILL
10-12 July 2023**

The Compact Accelerator based Neutron Source (CANS) project “LvB” at Martonvásár, Hungary

Private investment + Regional Industrial Development Grant
(Hungarian government & EU structural funds)

Consortium: **Mirrotron Ltd. (project leader)**
ELKH Center for Energy Research (CER)

Timeline:

Grant application: Sep. 2016


Grant funding contribution approved: May 2017

Project start: Nov. 2017

Mandatory project completion deadline:

- Initially: **Nov. 30, 2021**

- Extended for Covid-19 related delays: **Dec. 31, 2022**



Budapest

Mirrotron Kft.

33 perc
35,2 km

Martonvásár

Mirrotron Kft.

Martonvásár

Budapest Liszt Ferenc Nemzetközi Repülőtér

Vecses

Gyál

Felsőpakony

Ócsa

Budapest

49 perc
49,9 km


Budapest Liszt Ferenc Nemzetközi Repülőtér

40 perc
59,2 km

Martonvásár



Project building since 2019



Martonvásár railway station:
25 min from central Budapest



8 perc
650 m

Mirrotron Kft.

Martonvásári
vasútállomás víztornya

Pápay Ágoston Általános
Iskola, Készségfejlesztő...

Martonvásár

Martonvásári víztorny

Fátölgyes kft

Acer Kft

Hortobágyi Ágnes
Gyógymasször...

D-TECH Kft.
Szervíz, raktár


Szami 2003. Kft

Martonvásári temet

Mirrotron Ltd. business plan for the LvB project:

- Neutron beam quality assurance tests for needs in own neutron research equipment production: saves ~ 100 k€/y (supermirrors, monochromators, detectors etc.)
- Neutron beam quality assurance tests for international partners
- Products and services for neutron source developments
- Neutron scattering experimental work for industrial customers:
 - reflectometry, neutron diffraction (phase 1)
 - neutron diffraction for stress scanning, SANS (phase x)
- Leasing of neutron beams for industrial applications
- Development of irradiation beamline for cancer therapy (BNCT)
- Manufacturing of components for neutron sources and production of turn-key CANS facilities / key components

LvB CANS project lay-out (patents pending)



Public procurement tenders (from mid 2018):

- Ion source + Low energy beam transfer
- 2.5 MeV accelerator, 20 mA peak
- RF amplifier
- Integration and controls

Mirrotron's own design and production:

- High energy beam transfer
- Target-moderator-reflector (TMR) system

Fast neutron production:

2.5 MeV	2.5 kW	3×10^{11} n/s
5.0 MeV	5.0 kW	3×10^{12} n/s

ESS @ 5 MW: 1×10^{18} n/s

LvB Project status by June 30 2023



Oct 2019
Project building and
utilities completed

LvB Project status by June 30 2023



Oct 2021

RF Amplifier delivered and tested at full power on a dummy load



Dec 2021


2.5 MeV RFQ accelerator parts delivered to project site



May 2022

Accelerator assembled, electrically and mechanically tested

LvB Project status by June 30 2023



June 2022

Control system with remote communication capability installed and tested



July 2022

RFQ accelerator connected to RF amplifier and tested at full power

LvB Project status by June 30 2023



Oct 2022


Ion source contracted manufacturer failed to deliver anything; contract cancelled

Temporary Solution

Commissioning will start at 1 mA proton beam current, using an available ion source of project partner CER, Budapest

LvB Project status by June 30 2023


LvB bi-spectral moderator lay-out



Nov 2022

Target-moderator-reflector system main components are designed, manufactured, and ready for testing

LvB moderator and cooling system



LvB Project status by June 30 2023



January 2023

Own produced borated-concrete shielding system is installed.



Temporary ion source is installed.


LvB Project status by June 30 2023



January 2023

**Project completion report to
grant administration submitted
(does not include commissioning)**

LvB Project status by June 30 2023



May 2023

Preparations for the neutron test of the LvB Target-moderator-reflector system at the new, Cold-Moderator Test Facility constructed @ BNC

LvB Project status by June 30 2023



June 2023 CMTF Test setup

The cryostat assembly (without hydrogen)
Cryostat installed at Ch4

The moderator in the reflector,
The moderator part with the neutron window



Further plans – short term

Solid Li target:

manufacturing ready and delivered, target cooling system in manufacturing

Target-moderator-reflector system:

test & planned completion of installation in Q3 2023

Lavender harvest:

~85% completed by 7th July 2023




Further plans – medium term

Funded beam lines

(design integration, new neutron optics, choppers, installation by Mirrotron Ltd.)

- TOF Reflectometer for testing neutron supermirrors:

- redesign & reconstruction of dismantled IN11
- sensitivity not better than 0.1 – 1 % reflectivity
- polarized neutron and polarization analysis capability options to be installed later




Further plans – medium term

Funded beam lines

(design integration, new neutron optics and installation by Mirrotron Ltd.)


- **Large detector solid-angle time-of-flight diffractometer:**
 - redesign & reconstruction of dismantled IN6
 - best intensity basic mode of operation
 - optional high-resolution capability by fast quasi-random beam modulation
- **Epithermal neutron beam source development for BNCT**

Equipment composition of BNCT



Proton beams accelerated in a linear accelerator with a length of about 7m react with beryllium within a neutron generator to generate neutrons. A lesion part is irradiated with energy-regulated neutrons. (Example of the BNCT apparatus of the University of Tsukuba system)

Principle of BNCT



By nuclear reaction of neutrons with boron, alpha rays and lithium particles are released to break cancer cells.

Further plans - long term

Envisaged upgrades, not yet funded.

- **Adding afterburner DTL proton accelerator for achieving 5 – 8 MeV proton beam energy on the target**
 - about 5 - 10 times more fast neutron produced in the target at same proton beam current
 - target design simplified by larger proton penetration depth
- **Installing a local solar power plant of about 0.5 MW peak power**
 - for environmentally more sustainable routine operation
 - for reduced operational energy costs on long term >5 years

Register and visit us during the event of

UCANS10

**10th International Meeting of the Union of Compact Accelerator-driven Neutron Sources
Budapest, 16-19. October 2023.**



Hosted by

MIRR•TR•N
THE WORLD OF NEUTRON



Centre for
Energy Research

<https://ucans10.org/>

Thank you for your attention!

Yes, we still supply supermirror neutron guides.